BRUHAT BENGALURU MAHANAGARA PALIKE

Name of Work:- Community property Maintenance (including Parks) in J P park in ward no.17

Description of Items	Unit	No	L (M)	B (M)	D (M)	Qty	Est .Cost Rs. 5.00 Lakhs Rate	Amount
Work no:-017-20-000024								
Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint.(Page - 266/ Item no.37.3)								
	Sqm							
Park Compound		1	102.00		2.10	214.20		
						214.20	**757.90**	**162342.18**
Basic Rate	715.00							
Area Weightage @ 6%	42.90							
	757.90							
2 Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer-in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) including cost of materials, labour, HOM complete as per specifications. (Page - 266/ Item no.37.2)								
Park Compound	m	54			2.10	113.40		
						113.40	**910.54**	**103255.24**
Basic Rate	859.00							
Area Weightage @ 6%	51.54							
	910.54							
3 Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint, including cost of materials, labour, HOM complete as per specifications. (Item N0. 37.4 Pg No 266).								
	m							
Park Compound		3	102.00			306.00		
						306.00	**432.48**	**132338.88**
Basic Rate	408.00							
Area Weightage @ 6%	24.48							
	432.48							
4 Providing and applying enamel metal paint two coat (excluding priming coat) on previously painted steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications (Item No. 15.74 Pg No. 123).								
	Sqm							
Park Compound		1	102.00		2.10	214.20		
						214.20	**100.70**	**21569.94**
Basic Rate	95.00							
Area Weightage @ 6%	5.70							

Description of Items	Unit	No	L (M)	B (M)	D (M)	Qty	Rate	Amount
	100.70							
Basic Cost (A)								419506.24
Tender Premium at 5% (B)								20975.31
Sub Total (C)								440481.55
Adding GST at 12% on (C)								52857.79
Project Management Consultancy 1%								4195.06
Miscellaneous								2465.60
Total								500000.00

Rupees five Lakhs only

CERTIFICATE

1 The Work spot has been inspected and the work found to be necessary
2 The Estimate is prepared as per the PWD SR 2018-19
3 The Provision made in estimate are adequate and essential
4 This area comes under BBMP limits.

Asst Engineer
Ward No- 17
BBMP

Asst Executive Engineer
yeshwanthpur Sub Division
BBMP

Executive Engineer
Rajarajeshwari nagar-Division
BBMP

ನಂ.: 64 ದಿನಾಂಕ: 27/5/2020
ರೂ. Rupees five lakhs Only
[5,00,000/-]
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜುರಾತಿ ನೀಡಿದೆ.

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ರಾಜರಾಜೇಶ್ವರಿ ನಗರ ವಿಭಾಗ
ಬಿ.ಬಿ.ಎಂ.ಪಿ., ಬೆಂಗಳೂರು-72

ನಂ.: 34 ದಿನಾಂಕ: 27/5/2020
ರೂ. Rupees five lakhs Only
[5,00,000/-]
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜುರಾತಿ :

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂ
ಬಿ.ಬಿ.ಎಂ.ಪಿ., ರಾಜರ
ನಗರ ವಿಭಾಗ, ಬೆಂ